

पूर्व मध्य रेल

**Office of the
General Manager/S&T
Hajipur**

No. ECR/S&T/MISC (Computer No.279039)


Date:21/02/2025.

**Sr.DSTEs,
DHN/DNR/DDU/SEE & SPJ,
East Central Railway.**

Sub:- Regarding relay failures in UFSBI block panel.

UFSBI block panel failure because of problems in relays used in the equipment are being reported from divisions. While all relay failures are being reported to RDSO, it is required that necessary measures be taken to minimize such failures. Paralleling of relay and button contacts in UFSBI block panel is one such measure. Accordingly, the following is advised:

- (i) Henceforth, paralleling of contacts of relay/button used in UFSBI block panel are to be ensured by all executing agencies like Construction, Works, RVNL, IRCON, Open Line etc. while commissioning any UFSBI block panel.
- (ii) Division to undertake paralleling of these relay/button contacts for existing UFSBI block panel to reduce such failure on account of relays.



(राकेश रंजन)

मुख्य सिग्नल इंजीनियर-I

Copy to - for information & necessary action.

- **CSTE/Works, CSTE/Con/South, CSTE/Con/North/MHX,**
- **CGM(S&T)/IRCON/PNBE, CGM(S&T)/RVNL/Ranchi, CGM(S&T)/RVNL/Bhopal,**
- **Dy.CSTE/Works- DHN/DNR, Dy.CSTE/Works/DDU-I, Dy.CSTE/Works/DDU-II,
Dy.CSTE/Works/HJP & Dy.CSTE/Works/HJP-II.**