SPECIAL INSTRUCTIONS/APPROVED SPECIAL INSTRUCTIONS

SL.NO.	INSTRUCTIONS	ISSUED BY	AUTHORITY	DATE	REMARKS
1.	CONDONATION FOR INFRINGING GRADIENT.	CRS	CRS'S LETTER No. 4237	03.02.65	OBTAINED FROM CRS. FRESH CONDONATION TO BE OBTAINED
	1) AS PER GR 3.42 TAKING OFF MORE THAN 1/2 OF THE SIGNAL POST. 2) RECEPTION FROM RKJE BY TAKING OFF LHS SIGNAL NO. 5-1/C OVER 2/3 OF THE SIGNAL POST. 3) RECEPTION FROM PKA SAND HUMP AND RECEPTION FROM RKJE BY GIVING SLOT TO THE SIGNAL POST. 4) RECEPTION FROM RKJE BY TAKING OFF LHS SIGNAL NO. 5-1/C OVER 2/3 OF THE OVERLAP TOWARDS SAND HUMP.				TO BE OBTAINED

SIP PREPARED IN CONNECTION WITH PANEL INTERLOCKING WORK.

	CHECKED			
COUNTER SIGNED	(P. S. SAHAY) DY.CSTE/D&D/HJP	(SANJAY KUMAR) Sr.DSTE/CORD./DHN/ECR	(AMRENDRA SINGH) Dy.CSTE/W/DHN/ECR	(ATIT KUMAR) S.S.T.E./D&D/HJP
	f COM/ECR/HJP			
APPROVED BY	(RAM BECHAN) CSTE/PLG./ECR/HJP			
	f CSTE/E.C.R./HJP			

C.R.S. SANCTION No.	12/5/VIII/19 DT-08.08.2019
COMP. DATE- 23.08.2019	

E.C. RAILWAY
DHANBAD DIVISION

AUTHORITY- PB ITEM No. 621 OF 2015-16

PRADHANKHUNTA LINK

SIP No.

ECR/SIP/DHN/069-LINK/2015

DRAWN BY	SCALE
	LONGITUDINAL:- 1cm = 10m. TRANSVERSE :- 1cm = 5m.
A.S.T.E./D&D/HJP	S.S.E./SIG/HJP
SSE/DRG	TO SUIT CE'S DRG.No. Y-21-2015

PANEL INTERLOCKING
SIGNAL INTERLOCKING PLAN
(MACLS. STD-II (R) CLASS-B)

ALT.	DESCRIPTION	REFERENCE	DRAWN	JE/DRG	SE/SIG	SSE/D	ASTE/D&D	SSTE/D&D	DY. CSTE/W&D	f COM/ECR	f CSTE/ECR	CRS'S SANCN. COMP. NO.&DT
IV	ALTERED COMPLETION DRAWING MADE UPTO ALT-III.	DY. CSTE/W/DHN/DN-CSTE/W/DHN/CN-26.11.662/1/CON/PT-XVIII DT- 18.09.2019										
III	COMPLIANCE OF CRS OBSERVATION OF ITEM-4	DY CSTE/W/DHN LETTER NO- SG.662/1/CON/PT XVIII DT. 18.07.2019			SSE/A	ASTE/P&S	SSTE/D&D	DY.CSTE/W&D	f COM/ECR	f COM/ECR	f CSTE/ECR	
II	(i) LOCATION OF 3M PANEL CLASS-II (ii) PROVISION OF T-GAZ (CLASS DM-G) WITH BPAC (CLASS DM-G) FOR BLOCK WORKING TOWARDS RAKHITPUR.	I- DY CSTE/W/DHN LETTER NO- SG.662/1/CON/PT XVIII DT- 10.6.2019 II- TO SUIT ESP NO-Y-21-2015 ALT-3 DT- 01.05.2019		3E/DRG	SSE/SIG	SSE/P&S	ASTE/P&S	ASTE/D&D	DY.CSTE/P&S	f COM/ECR	f CSTE/ECR	
I	ALTERATION IN SIP FOR P-I WORK DETAILS OF L-KING MENTIONED.	VIDE DY. CSTE/W/DHN LETTER No- SG-662/1/Con/Pt XVII Dated 16/10/2018										

NOTE:-
1. ABSOLUTE BLOCK SYSTEM OF WORKING WITH RAKHITPUR.
2. BPAC 66/62 (A) WITH USSB-1 & 3M PANEL BETWEEN PRADHANKHUNTA LINK & RAKHITPUR.
3. MAGNETO TLEPHONE CONNECTED WITH PANEL ROOM & PRADHANKHUNTA Jn.
4. CONTROL TELEPHONE PROVIDED AT PANEL ROOM.
5. LED SIGNAL LAMPS TO BE USED.
6. S-8 OF PKA TO 'C' ROUTE IS RELEASED BY S-16 OF LNK CABIN AND S-1 & S-3 OF LNK CABIN IS RELEASED BY S-13 OF PKA.