

NOTE :-

1. ABSOLUTE BLOCK SYSTEM OF WORKING WITH CHANDRAPURA,TUPKADIH & BHANDARIDAH STN.
2. SINGLE LINE TOKENLESS BLOCK INSTRUMENT WORKING WITH CHANDRAPURA, & TUPKADIH FOR BOTH NORTH LINE & SOUTH LINE & BHANDARIDAH STN.
3. ALL ANGLE OF CROSSINGS ARE 1 IN 12 EXCEPT AS MENTIONED.
4. CONTROL TELEPHONE PROVIDED AT PANEL CABIN.
5. BPAC PROVIDED BETWEEN TUPKADIH-RAJABERA,(IN NORTH ROAD & SOUTH ROAD), BHANDARIDAH-RAJABERA & RAJABERA-CHANDRAPURA(NORTH COMMON LINE & SOUTH COMMON LINE) & INTERLOCKED WITH BLOCK INSTRUMENT.
6. TRACK CIRCUIT NO.3T,4T; 1T-2T ; 5T-5T1;6T- 9T; & 7T-7T1 ARE STAGGERED BY 1.82M.
7. FOR DETECTION OF TRACK ON DAMODAR RIVER AXLE COUNTERS ARE PROVIDED.

PANEL DETAILS:-

MAIN SIGNAL BUTTONS	1,2,3,4,5,6,7,9,10,12
CALLING - ON SIGNAL BUTTONS	C-1,C-3,C-9,C-10,C-12
POINT BUTTONS	51,52,53.
CRANK HANDLE CONTROL BUTTONS	CH-1,CH-2,CH-3

CH-1 CRANK HANDLE FOR PT 51 · CH-2 CRANK HANDLE FOR PT 52 · CH-3 CRANK HANDLE FOR PT 53

ALL CRANK HANDLE WELDED WITH KEY AT PANEL ROOM

SPECIAL INSTRUCTION / APPROVED SPECIAL INSTRUCTION

SL.NO	INSTRUCTION	ISSUED BY	AUTHORITY	REMARKS
1*1	SIG. NO. 4 PLACED ON R.H.S		IN TERMS OF GR.3 04(1) COM	SPECIAL SANCTION TO BE OBTAINED FROM COM/HJP.
ALT-II 2.	GRADIENT OF 1 IN 260 EXISTS IN STATION YARD.		DY. CRS/E.CIRCLE L. No. 16/A/75/VIII/563/H DT.12.2.14	CONDONATION TO BE OBTAINED FROM CRS/E CIRCLE /KOLKATA

ALT	DESCRIPTION	REFERENCE	CHECKED BY SSE/S/C/MHX	ASTE/C/MHX	SSTE/C/MHX	DY.CSTE/C/SOUTH/MHX	COUNTER SIGNED BY CSTE/C/S/MHX	f COM/ECR/HJP	APPROVED BY f CSTE/ECR/HJP	CRS SANCTION NO. & DATE	DATE OF COMM.
I.	GOODS WARNING BOARD TOWARDS MURI END PLACED AT 1700 METERS	Sr. DOM/PLG/DHN NOTE NO-TS/254/SWR/59/2013 dt. 4.10.2013		(R.K. SINGH)	(SMS SHAMSI)	(A.K. AMBASTHA)	03.10.13 (P. S. Rai)	9/4/14	10.4.14		
II.	COMPLIENCE OF CRS OBSERVATION.	L/No. 16/A/75/VIII/14/563/H Dt-12/2/14	(S. KUMARI)	(N. SHAMS)	(SMS SHAMSI)	(SATENDRA KUMAR)	(P. S. RAI)	9/4/14	10.4.14		
III	COMPLETION DRAWING MADE UPTO ALT-II.	VIDE ASTE/C/MHX/L-NO-ECR/S&T/CON/COMPLETION/DRG/15, DT-23.12.2015.	SSE/S JE/D	ASTE/DSD 20.01.16	SSTE/DSD 25/1/16	DY.CSTE/DSD 25.1.16			(S.D. PRASAD) CCE/ECR/HJP f CSTE/ECR/HJP	16/75A/VIII/14/205/H DT-05.08.14	13.12.14

THIS SIP SUREPCEDES PREVIOUS SIP NO. ECR/SIP/DHN/271/2006 ALT-I
AUTHORITY OF WORK:-PB ITEM NO. 43 OF 2012-13"

पूर्व मध्य रेल धनबाद मंडल EAST CENTRAL RAILWAY DHANBAD DIVISION	APPROVED BY	COUNTER SIGNED BY		CHECKED BY				C.R.S. SANCTION NO.	SCALE			
	(RAJESH-KUMAR) CSTE/W/ECR/HJP FOR CSTE/ECR/HJP	(P.S. RAI) CSTE/C/S/MHX	(NEERAJ AMBASTHA) CTPM/ECR/HJP f COM/ECR/HJP	(A.K. AMBASTHA) DY.CSTE / CON/S / MHX	(SMS. SHAMSI) SSTE / CON / MHX	(N.SHAMS) ASTE / CON / DNR	(S KUMARI) SSE / S / CON / MHX	16/A/75A/VIII/14/205/H DATE :- 05-08-2014 COMPLETED ON:- 13/12/2014.	LONGITUDINAL : 1CM = 10M TRANSVERSE : 1CM = 5 M	CENTRAL PANEL SIGNAL INTERLOCKING PLAN MACLS, CLASS-B,STD-II ®	राजाबेरा ब्लॉकहट RAJABERA BLOCK HUT	SIGNALLING PLAN NO. ECR/SIP/DHN/271/2013

BASED ON - CE'S. DRG. NO.- Y-10-2013 (ALT-I)

PREPARED BY - SHREE TRADING JAWAHAR NAGAR WEST BAILEY ROAD, PATNA 09007826420,9470247328,9905762538