पूर्व मध्य रेल

Office of the
General Manager(S&T)
Hajipur

File No: ECR-HQ0SnT(POLI)/2/2024
(Computer No: 170492)

Dated 04/07/2025.

Divisional Railway Manager,
DDU/DHN/DNR/SEE & SPJ,
East Central Railway.

Signal Policy No. 09/2025

Sub: Protection of damage to S&T installation on entangling of Lifting barrier boom with OHE during boom dashing.

It has been noticed in the recent past that lifting barrier booms of LC gates got entangled with OHE wire after being dashed by road vehicle at HPO, BMKI, MKPR & KVC stations of SPJ division. This resulted in damage to S&T installation thereby causing heavy disruption of train traffic

As an immediate measure, it has been decided to connect lifting barrier pedestals of all interlocked gates to the negative rail using TRD bonds. This is in addition to earthing of the gate pedestal to provide path to OHE current to return to its source.

You are therefore requested to please ensure that this connectivity is provided at all the LC gates to ensure safety of staff & equipment and compliance may be sent to this office at the earliest.

Savita Sanjay Gedam

Digitally signed by Savita Sanjay Gedam
Date: 2025.07.05 11:14:31 +05'30'

(Savita Gedam)
PCSTE/ECR

Copy to-

- **PCEE-for kind information please.**
- **CSTE/C//MHX, CSTE/C/N/MHX, Sr.DSTES-DDU/DHN/DNR/SEE & SPJ- for information & necessary action.**