



- NOTE:-**
1. ABSOLUTE BLOCK SYSTEM WORKING WITH SARAI & GORAU.
 2. DL UFSBI WITH SARAI & DL LOCK & BLOCK INSTRUMENT WITH GORAU STN. LOCATED AT SM ROOM.
 3. MAGNETO TLRFONE PROVIDED BETWEEN SM ROOM AND L.C GATE NO.29,30,31,33,34,35,36&37.
 4. CONTROL TELEPHONE PROVIDED AT SM ROOM.
 5. LED SIGNAL PROVIDED FOR ALL MACLS SIGNALS.
 6. DEAD APPROACH LOCKING PROVIDED FOR ALL INTERLOCKED GATES WITH 60 SEC TIME DELAY.
 7. 60 SEC. TIME DELAY PROVIDED FOR CALLING-ON RECEPTION SIG. NO. C-1 & C-12.
 8. ADDITIONAL INTERLOCKED SLIDING BOOM PROVIDED AT LC.NO.31,33 & 34.
 9. INSULATION JOINT IS PROVIDED 3M BEYOND STARTER SIGNAL.
 10. TWO CPU & VDU (ONE STAND BY) PROVIDED IN SM ROOM FOR PANEL OPERATION IN LIEU OF CONTROL CUM INDICATION PANEL AND ONE COLOUR MONITOR PROVIDED IN MAINTENANCE ROOM.

EAST CENTRAL RAILWAY SONPUR DIVISION	STATION WORKING RULE DIAGRAM MACL STD-II CLASS-'B'		BHAGWANPUR	SWRD NO.
	DSTE/ECR/SEE SSE/DRG/SEE SE/DRG/SEE TO SUIT SIP NO,ECR/SIP/SEE/133/2018, ALT-'I'			